

JUN 1 0 2016

CENTRAL OFFICE

APPENDIX A

ELECTRICIAN

D.O.T. CODE 824.261-010 O*NET CODE 47-2111.00

As Revised for Electricians JATC of Watertown – IBEW LU #910

This training outline is the current standard for Work Processes and Related Instruction. Changes in technology, regulations, and safety/health issues may result in the need for additional on-the-job or classroom learning.

WORK PROCESSES

		Approximate Hours
A.	Project Layout and Planning	200
	 Reading and interpreting blueprints and specifications. Coordination between crafts, engineers and architects. Laying out feeders, risers and branch circuits. 	
В.	<u>Underground Installations</u>	300
	 Trenching and ditch digging (if in keeping with prevailing area practice). Direct burial. Installing PVC/rigid conduit (including bender usage). Installing grounding electrode systems. 	
C.	Thinwall Conduit Raceway Systems	1,000
	 Selecting and installing fastening and support devices. Conduit fabrication. Installation of conduit, fittings and boxes. 	

	 Rigid Conduit Raceway Systems Selecting and installing fastening and supporting devices. Bender machine setup and operation. Conduit fabrication. Installation of conduit, fittings and boxes. Installing Services, Switchboards and Panels	750 EFFECTIVE APPRENTICE TRAINING JUN 1 0 2016 CENTRAL OFFICE 500
	 Mounting devices. Breaker installation. Terminations. 	
F.	 Shooting transit/grade establishment (if in keeping with prevailing area practice). Installing duct and fittings. Core drilling and outlet installation. 	200
G.	 Motor Control Center Installation Rigging and mounting (if in keeping with prevailing area practice). Terminating feeders, branch circuits and control wiring. 	100
Н.	 Installing, Splicing and Terminating Wires and Cables Establishing temporary power. Installing feeders and branch circuits. Installing control wiring. Performing splices, taps and terminations. 	1,200
I.	 Cable Tray Installation Fabrication. Installing support devices. Installing cable tray and covers. 	150
J.	 Lighting System Installation Installing outlet boxes and conductors. Installing fixtures and lamps. Installing lighting control devices. 	1,050

K. Testing and Troubleshooting Feeders, Motors, and Branch Circuits **EFFECTIVE** 1. Checking circuit continuity. APPRENTICE TRAINING 2. Identifying fault current to ground. JUN 1 0 2016 3. Meggering and Hi Potting. 4. Certifying system operation. CENTRAL OFFICE 5. Repair and maintenance. 6. Ground verification. L. Fire Alarm and Security System Installation (optional*) 300 The employer(s) for whom the apprentice or journeyperson is working must possess a valid Alarm Installer license, issued by the New York State Department of State. In addition, the apprentice/journeyperson performing such work must be fingerprinted, as required by the Department of State. 1. Fire Alarms (300 hrs.) a. Interpreting blueprints and specifications. b. Layout and circuit installation. c. Control panel and device installation. d. Programming and testing. 2. Security Systems (100 hrs.) a. Interpreting blueprints and specifications. b. Layout. c. Box and circuit installation. d. Terminations. e. Testing. M. Motor Installation 400 1. Rigging and setting (if in keeping with prevailing area practice). 2. Alignment (if in keeping with prevailing area practice). 3. Installing circuiting and terminations. 4. Testing. N. Control System Installation 200 1. Blueprint and specification interpretation. 2. Layout and circuit installation. 3. Installing and certifying distributed control system.

O.	Installing and Programming Programmable Logic Controllers	100 EFFECTIVE APPRENTICE TRAINING
	 Module installation. Installing control wiring and devices. Programming (if in keeping with prevailing area practice). 	JUN 1 0 2016 CENTRAL OFFICE
P.	Installing Instrumentation and Process Control Systems (if in keeping with prevailing area practice).	200
	 Blueprint and specification interpretation. Layout and installation. Calibration. 	
Q.	Installing Sound and Communication Systems	150
	 Blueprint and specification interpretation. Layout. Conduit and box installation. Installing panels and network devices. Circuit installation. Terminating and testing circuits. 	
R.	Installing and Terminating Transformers	100
	 Rigging and mounting (if in keeping with prevailing area practice). Terminating primary and secondary cables. Testing and troubleshooting. 	
S.	Installing Fiber Optic and Tele/Data Cable	100
	 Equipment layout. Installing cable. Polishing and terminating. Testing and verifying. 	
T.	Welding/Exothermic Welding and Brazing, Mechanical Fastening	100
	 Machine setup. Fabrication. Welding/exothermic welding, grinding and finishing. Installing fixings, fasteners and supports. 	

U. Service and Troubleshooting

Testing, analysis and repair of electrical/electronic components of: motors, transformers, electrical devices, electronic devices, magnetic devices, lighting and power circuits, equipment and machinery, control circuits and devices. EFFECTIVE APPRENTICE TRAINING

JUN 1 0 2016

CENTRAL OFFICE

V. Material Handling and Pre-Fabrication

1. Awareness of materials and equipment of the trade.

- 2. Handling materials of the trade (if in keeping with prevailing area practice).
- 3. Fabrication for field installation.
- 4. Cleanup and recycling.

W. <u>Safety Awareness</u>, <u>Processing Required Paperwork and Other Specialized Areas</u>

200

200

150

X. Green Skills (optional*)

200

- 1. Energy Efficiency (100 hrs.)
 - a. Replacing incandescent light bulbs with compact fluorescent lamps (CFL's), while maintaining or improving lighting levels.
 - b. Properly installing smoke detectors.
 - c. Properly installing carbon monoxide (CO) detectors.
 - d. Checking electrical appliances for obstruction, dilapidation or other contributing factors to energy waste.
 - e. Building automation:
 - 1. Correctly interpreting blueprints and specifications.
 - 2. Layout and circuit installation.
 - 3. Selecting and installing fastening and support devices.
 - 4. Installing all electrical components and control devices.
 - 5. Applying system integration with open protocols.
 - 6. Bonding and grounding of all electrical components.
- 2. Alternative Energy Sources-solar, wind, fuel cell, etc. (200 hrs.)
 - a. Working safely with alternate energy systems.
 - b. Conducting a site assessment including possible barriers such as: wind, property location, height, sunlight (if applicable).
 - Accurately reading blueprints, specifications, drawings, schematics, work orders, and/or recommended procedures.

JUN 1 0 2016

CENTRAL OFFICE

e. Adapting, planning, layout, design and circuit installation.

d. Selecting appropriate materials and amounts based on

- f. Selecting and installing fasteners and supportive devices (if applicable).
- g. Installing racking systems (if applicable).
- h. Installing modules, inverters (if applicable).
- i. Assembling, installing, weather scaling photovoltaic systems and support structures (if applicable).
- j. Installing fuel cells (if applicable).
- k. Installing wind turbines (if applicable).
- 1. Bonding and grounding.

requirements of job.

m. Inspecting, testing, verifying, maintaining, troubleshooting, repairing systems.

> Total Minimum Hours of On-the-Job Training (over a five-year period)

8.000

*It is expected the apprentice will complete some, but not all, of the optional work processes.

Apprenticeship work processes are applicable only to training curricula for apprentices in approved programs. Apprenticeship work processes have no impact on classification determinations under Article 8 or 9 of the Labor Law. For guidance regarding classification for purposes of Article 8 or 9 of the Labor Law, please refer to http://www.labor.state.ny.us/workerprotection/publicwork/PDFs/Article8FAQS.pdf.

JUN 1 0 2016

CENTRAL OFFICE

APPENDIX B

RELATED INSTRUCTION

ELECTRICIAN

(Courses may be taken in a different order from that described below.)

Safety

Safety and Health Awareness (safeguarding both worker and the public)
OSHA/Safety Awareness (including fall-protection and confined space training)
OSHA 10-Hour Construction Course – if required for Public Work
Asbestos Awareness – minimum 4 hours (see attachment)
First Aid/CPR – minimum 6.5 hours every 3 years
Proper Use of Personal Protective Equipment (PPE)
Right-to-Know/Material Safety Data Sheets (MSDS)

Blueprints

Blueprint Reading and Sketching CAD (optional)

Mathematics

Algebra Geometry Trigonometry Trade Math Estimating (optional)

Trade Theory

Electrical Theory

Fiber Optics

Trade Science

Tools and Equipment: Safety, Proper Use, Care and Maintenance National Electrical Code State and Local Electrical Codes Conduit Fabrication Transformers Electrical Grounding Electronics Motors Digital Electronics

JUN 1 0 2016

CENTRAL OFFICE

Motor Control
Distributed Control

Intelligent Wiring Systems

Local Area Network Systems

Low Voltage Systems

Programmable Logic Controllers

Telecommunications

Fire Alarm and Security Systems (if Work Process "L" is selected)

Installations: Standards, Codes and Techniques,

Control Panels and Alarm Transmissions,

Security Systems and Fire Technology

Welding for the Trade

Systems Analysis, Repair and Certification

Air Conditioning

Instrumentation

Process Control

Service and Troubleshooting

Building Automation (if Work Process "X" is selected)

Alternate Energy Sources (Solar, Wind, Fuel Cell, etc.): Installation and Repair (if Work Process "X" is selected)

Lighting Controls

Energy Efficiency (if Work Process "X" is selected)

Demand Limiting

Customer Service

Workmanship

Sexual Harassment Prevention Training – minimum 3 hours

A minimum of 180 hours of Related Instruction is required for each apprentice for each of the five years. This results in a total of at least 900 hours.

ATTACHMENT TO APPENDIX B

JUN 1 0 2016

CENTRAL (-

Asbestos Awareness

This course must be delivered by one of the following:

- 1. A provider currently approved by the New York State Department of Health to deliver asbestos safety training.
- 2. A person holding a current Asbestos Handler certificate from the New York State Department of Labor in the title of: Inspector, Supervisor, Project Monitor, Management Planner, or Project Designer.
- 3. Anyone otherwise approved by the New York State Education Department.

Minimum course contents must include the following:

- 1. Definition of asbestos
- 2. Types and physical characteristics
- 3. Uses and applications
- 4. Health effects:

Asbestos-related diseases Risks to families Cigarette smoking Lack of safe exposure level

5. Employer-specific procedures to follow in case of potential exposure, including making a supervisor or building owner immediately aware of any suspected incidental asbestos disturbance so that proper containment and abatement procedures can be initiated promptly.

Notwithstanding the above course requirement, employers are advised that they must also be in compliance with New York State Department of Labor Industrial Code Rule 56 at all times.

Employers are further advised, and must advise all apprentices, that completion of the above course requirement does not authorize any person to remove, encapsulate, enclose, repair, disturb, or abate in any manner, any friable or non-friable asbestos, asbestos containing material, presumed asbestos containing material, or suspect miscellaneous asbestos containing material.